

19. What exactly is included in the basic bay (USD 3,625) and in the classic bay (USD 7,090)? Do they include the LED edge strips, the printed graphics and the roof? On the classic model, is the top signage band illuminated (LED) or only printed?

The Basic Version includes the **floor, structural frame, roof, 5 sets of non-illuminated lettering, and 2 manual roller shutter doors** for the entrance and exit.

The Classic Version includes everything in the Basic Version, with the addition of **831-type integrated color-coated steel ceiling panels**.

Normally, the decorative lettering is **non-illuminated lettering** rather than printed graphics. Illuminated lettering is also available as an optional upgrade.

20. Roof material. Is an insulated (sandwich panel) roof available? My site has direct sun at 50 C.

The roof uses **50 mm** thick glass wool insulation with a density of **14 kg/m³**, covered by an external metal cladding. This structure provides effective thermal insulation and significantly reduces heat transfer from direct sunlight compared with a single-layer metal roof.

For temperatures around 50°C, this insulation structure is **generally sufficient for normal use**.

If you prefer a sandwich panel roof, an additional roof structure would need to be installed, which would involve extra cost.

The specific cost can be confirmed later when we finalize the order details, together with the extended pre-house option.

21. Wind load rating of the structure and anchoring to the slab (type and number of bolts).

The wind load resistance can generally reach around **0.6 kN/m²**.

The structure is **not mechanically anchored to the concrete floor**. It is placed directly on a level surface.

Inside the car wash bay, the base area will be **filled with concrete**, which is used to form the internal drainage system and guide wastewater toward the drainage outlet.

22. Wall panels front and back (USD 357): where exactly do they go? Please send a drawing.

They can be installed **around the sides** of the bay or at **the entrance and exit**, mainly for customers who do not require glass walls.

As for the installation drawings, the supplier will provide the detailed drawings **after** payment has been made.

23. Illuminated letters (5 sets): which are the 5 positions and can I use my own name and logo instead of "Cheer Wash"?

You can use **your own name or logo**, but it can only be made in the form of **letters/text-shaped signage**. Image-style graphics cannot be produced in this way.

For the **Basic version**, the illuminated lettering is mainly installed on the **columns of the pre-house**.

For the **Classic version**, it can be installed on the **top decorative structure**.

24. Tempered glass: can I order only 2 of the 4 sets (one side only)? In that case, what closes the other side, and what is the price of a solid side wall panel for it?

Yes, **that is possible**. The other two sides can be covered with the **wall panels front and back** instead of glass panels.

25. LED light ZT5018: one set is 2,400 x 4,800 mm. Do I need 2 sets to cover a 9.3 m bay, and how are they mounted to the bay roof?

Yes, but there's no need to cover the entire area. Just like in a room, **one light placed in the center can provide enough illumination for the whole space.**

26. Prefab control room 2 x 3 x 3 m: wall and roof material, thermal insulation, can I hang a mini-split air conditioner on the wall, does it come with floor, lockable door, ventilation and openings for pipes and cables? What do I need to do on site?

The walls are made of **rock wool sandwich panels**, while the roof consists of **glass wool insulation with metal cladding**, providing good thermal insulation.

An air-conditioning system **can be added** if required. The structure comes with **a floor and a door**, but does not include a ventilation system. Ventilation can be provided through the windows if needed.

There are **no pre-reserved ventilation openings**, so any required openings would need to be made on site.

After the structure arrives at the site, the customer will need to **complete the foundation and connect the water and electricity supplies.**

27. Are the bay and the control room assembled on site or delivered assembled? How many people and days does assembly take?

Both the car wash bay and the control room need to be assembled **on site**. The installation will require approximately **4 workers** and about **one week** to complete. The installation time is roughly the **same as** that required for our car wash machine.